

市道十日市245号線道路修繕工事数量計算総括表

工 種	種 別	規 格	単位	計算数量	設計書数量
土 工					
	床 掘	小規模 礫質土	m³	10.80	11.0
	埋 戻	小規模 礫質土	m³	9.36	9.0
	運 搬	礫質土 L=8.0km	m³	0.40	0.4
取 壊 工					
	舗 装 切 断	t=15cm以下	m	25.00	25.0
	舗 装 取 壊	機械	m²	12.00	12.0
	舗 装 殻 運 搬	L=5.8km	m²	0.72	1.0
	構 造 物 取 壊	無筋	m²	3.84	4.0
	Co 殻 運 搬	無筋 L=11.7km	m²	3.84	4.0
処 分 工					
	残 土		m³	0.40	0.4
	A s 殻		t	1.69	2.0
	C o 殻	無筋	t	9.02	9.0
側溝設置工					
	側 溝	FXまたはDCT 400 * 600	m	24.00	24.0
	ケレーチング設置	400用 L=1000	枚	15.00	15.0
	コンクリート蓋設置	スリット入 400 L=500	枚	18.00	18.0
	インハートコンクリート		m³	0.48	0.5
	間詰コンクリート		m³	0.96	1.0
舗 装 工					
	路 盤 工	車道 M-30 t=10cm	m²	13.68	14.0
	表 層 工	車道 再生密粒As13 t=4cm	m²	13.68	14.0
安 全 費					
	交 通 誘 導 員		人	6.00	6.0

土 工 数 量 計 算 書

測 点	距 離	床 掘			埋 戻					
		断面	平均	立積	断面	平均	立積			
0.0		0.45			0.39					
24.0	24.0	0.45	0.45	10.80	0.39	0.39	9.36			
計	24.0 m			10.80 m ³			9.36 m ³			m ³

取壞工 数 量 計 算 書

[illegible]

取壊工数量計算書

測 点	距 離	構造物取壊工(無筋)			構造物取壊工(有筋)					
		断面	平均	立積	断面	平均	立積		平均	
0.0		0.16								
24.0	24.0	0.16	0.16	3.84						
小計	24.0			3.84	m3		0.00			

鋪装工数量計算書

[illegible]

延長数量計算表

舗装切断						
測 点		延長	摘要	測 点	延長	延長
0.0		0.5				
24.0		24.0				
		0.5				
計		25.0 m			16.0	0.00

延長数量計算表

側溝

測点	400 * 600					
0.0						
24.0	24.0					
計	24.0					

側溝工 数 量 計 算 書

[illegible]

延長数量計算表

ゲレチング				コンクリート蓋版(400)		
測 点	300		摘要	測 点	枚数	摘要
0.0				0.0		
9.5	1.0			9.5	17.0	
23.5	14.0			23.5		
24.0				24.0	1.0	
計	15.0				18.00	枚

土量分配表



