

## 集計表

項目	規格	単位	数量	計上数量	備考
舗装工					
	すきとり	m3	76.1	80	1522.92*5cm
	不陸整正	m2	1,522.9	1520	
	基層	m2	1,522.9	1520	
	表層	m2	1,522.9	1520	
	すり付け舗装(t=25mm)	m2	0.0	0	
	すり付け舗装(t=45mm)	m2	0.0	0	
	薄層カラー舗装	m2	97.0	97	
区画線工					
	実線 15cm	m	436.0	440	
	破線 15cm	m	0.0	0	
	実線 20cm	m	218.0	220	
	実線 45cm(青)	m	15.0	15	
舗装版取壊工					
	舗装版破碎 t=5cm	m2	1,522.9	1520	
	ダンプトラック運搬(As)	m3	76.1	76	
	処分費(As)	t	178.9	179	
	舗装版切断	m	36.0	36	
安全費					
	交通誘導員	人	27.0	27	

## 集計表

施工箇所	羽出庭三良坂線													
測 点	延 長	アスファルト剥取			不陸整正			基層			表層			
		t=50mm						再生粗粒度As(20) t=50mm			再生密粒度As(20) t=50mm			
	(m)	幅 員	平均幅員	面 積	幅 員	平均幅員	面 積	幅 員	平均幅員	面 積	幅 員	平均幅員	面 積	
sect.0		6.86			6.86			6.86			6.86			切断6.9m
sect.54.5	54.5	6.90	6.88	375.0	6.90	6.88	375.0	6.90	6.88	375.0	6.90	6.88	375.0	切断10.6m*2
sect.00.4	45.9	6.90	6.90	316.7	6.90	6.90	316.7	6.90	6.90	316.7	6.90	6.90	316.7	
sect.135.5	35.1	6.80	6.85	240.4	6.80	6.85	240.4	6.80	6.85	240.4	6.80	6.85	240.4	
sect.159.8	24.3	7.21	7.01	170.3	7.21	7.01	170.3	7.21	7.01	170.3	7.21	7.01	170.3	
sect.190.3	30.5	7.20	7.21	219.9	7.20	7.21	219.9	7.20	7.21	219.9	7.20	7.21	219.9	
sect.201.0	10.7	7.20	7.20	77.0	7.20	7.20	77.0	7.20	7.20	77.0	7.20	7.20	77.0	
sect.218.0	17.0	7.34	7.27	123.6	7.34	7.27	123.6	7.34	7.27	123.6	7.34	7.27	123.6	切断7.3m

