

市道 川地91号線 道路舗装工事数量計算総括表

[illegible]

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3.0m以上			舗装工 W=1.4m～3.0m			舗装工 W=1.4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
川地91号線										
A箇所										
0.0					2.5					
35.0	35.0				2.5	2.5	87.5			
小計							87.5			
B箇所										
0.0					1.6					
20.0	20.0				1.6	1.6	32.0			
40.0	20.0				1.6	1.6	32.0			
60.0	20.0				1.6	1.6	32.0			
80.0	20.0				1.5	1.6	31.0			
100.0	20.0				1.5	1.5	30.0			
120.0	20.0				1.3	1.4	28.0			
140.0	20.0				1.4	1.4	27.0			
146.0	6.0				3.1	2.3	13.5			
147.0	1.0				1.1	2.1	2.1			
小計							227.6			
川地106号線										
0.0					2.9					
50.0	50.0				2.9	2.9	145.0			
96.0	46.0				2.9	2.9	133.4			
100.0	4.0				3.9	3.4	13.6			
104.0	4.0				2.9	3.4	13.6			
150.0	46.0				2.9	2.9	133.4			
200.0	50.0				2.9	2.9	145.0			
238.0	38.0				3.0	3.0	112.1			
242.0	4.0				3.4	3.2	12.8			
246.0	4.0				3.0	3.2	12.8			
250.0	4.0				2.9	3.0	11.8			
300.0	50.0				2.9	2.9	145.0			
350.0	50.0				2.9	2.9	145.0			
小計							1,023.5			