

## 集計表

項目	規格	単位	数量	計上数量	備考
舗装工					
	すきとり	m3	125.1	130	2501.6*5cm
	不陸整正	m2	2,501.6	2500	
	基層	m2	2,501.6	2500	
	表層	m2	2,501.6	2500	
区画線工					
	実線 15cm 白	m	1,068.0	1070	
	実線 45cm 白	m	30.5	31	
舗装版取壊工					
	舗装版破碎 t=5cm	m2	2,501.6	2500	
	ダンプトラック運搬(As)	m3	125.1	125	
	処分費(As)	t	293.9	294	
	舗装版切断	m	59.1	59	
安全費					
	交通誘導員	人	30.0	30	

## 集計表

施工箇所	羽出庭三良坂線				A箇所									
測 点	延 長	アスファルト剥取			不陸整正			基層			表層			
				t=50mm				再生粗粒度As(20) t=50mm		再生密粒度As(20) t=50mm				
	(m)	幅 員	平均幅員	面 積	幅 員	平均幅員	面 積	幅 員	平均幅員	面 積	幅 員	平均幅員	面 積	
sect.0		6.80			6.80			6.80			6.80			切断6.8m
sect.50.0	50.0	6.80	6.80	340.0	6.80	6.80	340.0	6.80	6.80	340.0	6.80	6.80	340.0	
sect.85.0	35.0	6.80	6.80	238.0	6.80	6.80	238.0	6.80	6.80	238.0	6.80	6.80	238.0	切断3.50m
sect.100.0	15.0	6.75	6.78	101.7	6.75	6.78	101.7	6.75	6.78	101.7	6.75	6.78	101.7	
sect.150.0	50.0	6.90	6.83	341.5	6.90	6.83	341.5	6.90	6.83	341.5	6.90	6.83	341.5	
sect.200.0	50.0	7.20	7.05	352.5	7.20	7.05	352.5	7.20	7.05	352.5	7.20	7.05	352.5	
sect.215.0	15.0	7.90	7.55	113.3	7.90	7.55	113.3	7.90	7.55	113.3	7.90	7.55	113.3	
sect.232.0	17.0	6.75	7.33	124.6	6.75	7.33	124.6	6.75	7.33	124.6	6.75	7.33	124.6	
sect.250.0	18.0	6.70	6.73	121.1	6.70	6.73	121.1	6.70	6.73	121.1	6.70	6.73	121.1	
sect.300.0	50.0	6.65	6.68	334.0	6.65	6.68	334.0	6.65	6.68	334.0	6.65	6.68	334.0	
sect.306.0	6.0	6.65	6.65	39.9	6.65	6.65	39.9	6.65	6.65	39.9	6.65	6.65	39.9	切断6.65m

## 集計表

[illegible]

