

排水構造物工 集計表		
名 称 ・ 規 格	数 量	合 計
作業土工		
床掘 E(SE)		34.6 m ³
埋戻し Fu(C)		0.0 m ³
埋戻し Fu(D)		24.4 m ³
埋戻しコンクリート Fu(Co)		0.0 m ³
基面整正 K(SE)		59.6 m ²
側溝工		
プレキャスト側溝 PL2-250B		0.0 m
PU3-B300-H300		120.0 m
側溝蓋 PC4-B300		20.0 枚

排水構造物工 数量計算書											(作業土工)	本線
種 別 番 号	距 離	E(SE)・右側			Fu(D)・右側			K(SE)・右側			摘 要	
		断面	平 均	数 量	断面	平 均	数 量	幅	平 均	数 量		
	—	0.1	—	—							土側溝	
NO. 3	8.3	0.1	0.10	0.8								
	4.9	0.1	0.10	0.5								
	—	0.3	—	—	0.3	—	—	0.5	—	—	PU3-B300-H300	
NO. 13	13.0	0.3	0.30	3.9	0.3	0.30	3.9	0.5	0.50	6.5		
BC. 4	5.0	0.3	0.30	1.5	0.3	0.30	1.5	0.5	0.50	2.5		
NO. 14	15.2	0.3	0.30	4.6	0.2	0.25	3.8	0.5	0.50	7.6		
SP. 4	6.8	0.3	0.30	2.0	0.3	0.25	1.7	0.5	0.50	3.4		
NO. 15	13.5	0.3	0.30	4.1	0.2	0.25	3.4	0.5	0.50	6.8		
	6.3	0.3	0.30	1.9	0.2	0.20	1.3	0.5	0.50	3.2		
	—	0.3	—	—	0.2	—	—	0.5	—	—	PU3-B300-H300	
EC. 4	1.3	0.3	0.30	0.4	0.2	0.20	0.3	0.5	0.50	0.7		
BC. 5		0.3			0.3			0.5				
SP. 5	12.6	0.3	0.30	3.8	0.2	0.25	3.2	0.5	0.50	6.3		
NO. 17	5.5	0.3	0.30	1.7	0.2	0.20	1.1	0.5	0.50	2.8		
EC. 5	7.1	0.3	0.30	2.1	0.2	0.20	1.4	0.5	0.50	3.6		
NO. 18	12.5	0.3	0.30	3.8	0.2	0.20	2.5	0.5	0.50	6.3		
BC. 6	10.3	0.3	0.30	3.1	0.2	0.20	2.1	0.5	0.50	5.2		
NO. 19	9.8	0.3	0.30	2.9	0.2	0.20	2.0	0.5	0.50	4.9		
SP. 6	22.7	0.3	0.30	6.8	0.2	0.20	4.5	0.5	0.50	11.4		
NO. 21	17.8	0.3	0.30	5.3	0.2	0.20	3.6	0.5	0.50	8.9		
EC. 6	14.7	0.2	0.25	3.7	0.2	0.20	2.9	0.5	0.50	7.4		
NO. 22	5.5	0.3	0.25	1.4	0.2	0.20	1.1	0.5	0.50	2.8		
BC. 7	8.7	0.3	0.30	2.6	0.2	0.20	1.7	0.5	0.50	4.4		
NO. 23	10.7	0.3	0.30	3.2	0.3	0.25	2.7	0.5	0.50	5.4		
小 計				34.6			24.4			59.6		

排水構造物工 数量計算書

(作業土工)

本線

種 別 番 号	距 離	E(SE)・右側			Fu(D)・右側			K(SE)・右側			摘 要
		断面	平 均	数 量	断面	平 均	数 量	幅	平 均	数 量	
	—	0.4	—	—	0.3	—	—	0.5	—	—	PU3-B300-H300
NO. 35	10.5	0.4	0.40	4.2	0.3	0.30	3.2	0.5	0.50	5.3	
SP. 12	5.0	0.3	0.35	1.8	0.2	0.25	1.3	0.5	0.50	2.5	
EC. 12	17.9	0.3	0.30	5.4	0.2	0.20	3.6	0.5	0.50	9.0	
BC. 13	12.2	0.3	0.30	3.7	0.2	0.20	2.4	0.5	0.50	6.1	
NO. 37	6.1	0.3	0.30	1.8	0.2	0.20	1.2	0.5	0.50	3.1	
SP. 13	10.5	0.3	0.30	3.2	0.2	0.20	2.1	0.5	0.50	5.3	
	8.3	0.3	0.30	2.5	0.2	0.20	1.7	0.5	0.50	4.2	
	—	0.2	—	—	0.1	—	—	0.5	—	—	PU3-B300-H300
EC. 13	7.5	0.2	0.20	1.5	0.1	0.10	0.8	0.5	0.50	3.8	
BC. 14	6.6	0.2	0.20	1.3	0.1	0.10	0.7	0.5	0.50	3.3	
NO. 39	4.9	0.2	0.20	1.0	0.1	0.10	0.5	0.5	0.50	2.5	
SP. 14	8.2	0.2	0.20	1.6	0.1	0.10	0.8	0.5	0.50	4.1	
EC. 14	13.0	0.2	0.20	2.6	0.1	0.10	1.3	0.5	0.50	6.5	
NO. 41	19.4	0.2	0.20	3.9	0.1	0.10	1.9	0.5	0.50	9.7	
BC. 15	9.3	0.2	0.20	1.9	0.1	0.10	0.9	0.5	0.50	4.7	
SP. 15	13.0	0.2	0.20	2.6	0.1	0.10	1.3	0.5	0.50	6.5	
EC. 15	13.0	0.2	0.20	2.6	0.1	0.10	1.3	0.5	0.50	6.5	
NO. 43	3.8	0.2	0.20	0.8	0.1	0.10	0.4	0.5	0.50	1.9	
	9.8	0.2	0.20	2.0	0.1	0.10	1.0	0.5	0.50	4.9	
小 計				0.0			0.0			0.0	
合 計				34.6			24.4			59.6	

[illegible]

第 表 PC4-B300 数量計算書					
左 側			右 側		
位 置	延長ヶ所	摘 要	位 置	延長ヶ所	摘 要
NO. 11+11.0～NO. 11+13.0	4.0		NO. 12+7.0～NO. 12+15.0	16.0	
NO. 40+4.9～NO. 40+7.9	6.0		NO. 16+3.5～NO. 16+8.3	9.0	
			NO. 21+18.5～NO. 22+4.0	11.0	
			NO. 41+18.1～NO. 42+2.2	8.0	
			NO. 42+10.7～NO. 43+9.9	38.0	
小 計	0.0	枚	小 計	20.0	枚
			合 計	20.0	枚