

[illegible]

舗装工 数 量 計 算 書

測 点	距 離	舗装工 W=3.0m以上			舗装工 W=1.4m～3.0m			舗装工 W=1.4m未満		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積
市道八次15号線										
0.0		16.7								
6.0	6.0	6.3	11.5	69.0						
20.0	14.0	4.5	5.4	75.6						
50.0	30.0	4.2	4.4	130.5						
83.0	33.0	4.1	4.2	137.0						
100.0	17.0	4.1	4.1	69.7						
150.0	50.0	4.1	4.1	205.0						
200.0	50.0	4.2	4.2	207.5						
232.0	32.0	4.2	4.2	134.4						
242.0	10.0	4.6	4.4	44.0						
250.0	8.0	4.3	4.5	35.6						
300.0	50.0	4.2	4.3	212.5						
350.0	50.0	4.2	4.2	210.0						
400.0	50.0	4.1	4.2	207.5						
450.0	50.0	4.2	4.2	207.5						
500.0	50.0	4.4	4.3	214.0						
550.0	50.0	4.3	4.3	216.5						
600.0	50.0	4.4	4.3	216.5						
650.0	50.0	4.2	4.3	214.0						
700.0	50.0	4.1	4.2	207.5						
750.0	50.0	4.3	4.2	209.0						
759.0	9.0	4.6	4.4	39.9						
768.0	9.0	4.4	4.5	40.5						
800.0	32.0	4.4	4.4	140.2						
850.0	50.0	4.3	4.3	216.5						
900.0	50.0	4.6	4.5	222.5						
911.0	11.0	4.6	4.6	50.6						
950.0	39.0	4.3	4.5	173.6						
1000.0	50.0	4.4	4.4	217.5						
1050.0	50.0	4.5	4.4	221.5						
1100.0	50.0	4.4	4.4	221.5						
1150.0	50.0	4.5	4.5	222.5						
1173.0	23.0	4.5	4.5	103.5						
1178.0	5.0	5.2	4.9	24.3						
1198.0	20.0	4.7	5.0	99.0						
小計				5216.9			0.0			0.0